



ཉལ། གནམ་གྱི་སླེལ་འདྲེན་ལམ་ལུང་སྐོར་
བཞུགས་པའི་འགྲུལ་འཕྲིན་ལྷན་ཁག་ དཔལ་ལྷན་འབྲུག་གཞུང་།
Department of Air Transport
Ministry of Information and Communication
Royal Government of Bhutan



Paro International Airport

18th November 2021

CORRIGENDUM NO. 1

Name of project: Runway resurfacing, extension and other related works in Bumthang Domestic Airport

1. Please read, Section 3, Page 3-6 as follows:

The bidder should submit evidence of line of credit worth Nu. 95.00 Millions from any authorized financial institutions specifically for the Project, valid till the project completion date.

2. Please find attached the revised milestone plan.

(Tashi Gyeltshen)

Offtg. Chief of Airport Development Division

MILESTONE WORK PLAN FOR RUNWAY RESURFACING AND EXTENSION AND OTHER ANCILLARY WORKS AT BUNTHANG DOMESTIC AIRPORT

| WBS | Task Name | Unit | Qty | 2022 | | | | | | | | | | | | | | | | | |
|------------|---|-------|-------|------|----|----|-----|----|----|-----|----|----|-----|----|----|-----|----|----|-----|----|----|
| | | | | Jan | | | Feb | | | Mar | | | Apr | | | May | | | Jun | | |
| | | | | W1 | W2 | W3 | W1 | W2 | W3 | W1 | W2 | W3 | W1 | W2 | W3 | W1 | W2 | W3 | W1 | W2 | W3 |
| 1.1 | 1 Resurfacing and other development works at BDA | | | | | | | | | | | | | | | | | | | | |
| 1.1.1 | Mobilisation | | | | | | | | | | | | | | | | | | | | |
| 1.1.1 | Site establishment | nos | 1 | | | | | | | | | | | | | | | | | | |
| 1.1.1.1 | Site Laboratory | nos | 1 | | | | | | | | | | | | | | | | | | |
| 1.1.1.2 | Site office | nos | 1 | | | | | | | | | | | | | | | | | | |
| 1.1.1.3 | Site stores | nos | 1 | | | | | | | | | | | | | | | | | | |
| 1.1.1.4 | Workers' camps | nos | 1 | | | | | | | | | | | | | | | | | | |
| 1.1.1.5 | Plants installation and testing | nos | 1 | | | | | | | | | | | | | | | | | | |
| 1.1.2 | Raw Materials | | | | | | | | | | | | | | | | | | | | |
| 1.1.2.1 | Gabion walls and fencing | bags | 2730 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.1 | Cement | bags | 355 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.2 | Sand | cum | 500 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.3 | Aggregates | cum | 500 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.4 | Boulders | cum | 11678 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.5 | Steel members | Kgs | 4950 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.6 | Concertina coils | mts | 32530 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.7 | Barbed wires | sqm | 3632 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.8 | Chain linked fencing | sqm | 16860 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.9 | GI double knotted mesh(gabion boxes) | sqm | 9450 | | | | | | | | | | | | | | | | | | |
| 1.1.2.1.10 | GI chainlink mesh(gabion boxes) | sqm | 9450 | | | | | | | | | | | | | | | | | | |
| 1.1.2.2 | Bitumen works | | | | | | | | | | | | | | | | | | | | |
| 1.1.2.2.1 | Aggregates | cum | 6870 | | | | | | | | | | | | | | | | | | |
| 1.1.2.2.2 | Sand | cum | 3885 | | | | | | | | | | | | | | | | | | |
| 1.1.2.2.3 | Bitumen | tonne | 810 | | | | | | | | | | | | | | | | | | |
| 1.1.2.2.4 | Cement | bags | 10615 | | | | | | | | | | | | | | | | | | |
| 1.1.3 | Testing | | | | | | | | | | | | | | | | | | | | |
| 1.1.3.1 | Bitumen | | | | | | | | | | | | | | | | | | | | |
| 1.1.3.2 | JMF | | | | | | | | | | | | | | | | | | | | |
| 1.2 | Fencing and Gabion wall | | | | | | | | | | | | | | | | | | | | |
| 1.2.1 | New Gabion wall with fencing on top including toe banking | mts | 760 | | | | | | | | | | | | | | | | | | |
| 1.2.2 | Toe banking in existing Gabion walls | mts | 1600 | | | | | | | | | | | | | | | | | | |
| 1.2.3 | Realignement of fencing(new) | mts | 1150 | | | | | | | | | | | | | | | | | | |
| 1.2.4 | Demolition of existing fencing | mts | 330 | | | | | | | | | | | | | | | | | | |
| 1.3 | Existing Runway with extension including apron | | | | | | | | | | | | | | | | | | | | |
| 1.3.1 | Jungle clearing(extension) | | | | | | | | | | | | | | | | | | | | |
| 1.3.2 | Earthwork in excavation in extended area full width | mts | 650 | | | | | | | | | | | | | | | | | | |

[Handwritten signature]

| | | | | | | | | | | | | | | | | | | | | |
|--------------------|--|-----|------|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| 1.3.3 | Embanking works over full length including side strips of existing runway | mts | 1600 | | | | | | | | | | | | | | | | | |
| 1.3.4 | Preparation of sub grade(extension) full width | mts | 650 | | | | | | | | | | | | | | | | | |
| 1.3.5 | Providing and Laying GSB(extension) full width | cum | 3500 | | | | | | | | | | | | | | | | | |
| 1.3.6 | Providing and Laying wet mix macadam(extension) full width | cum | 3100 | | | | | | | | | | | | | | | | | |
| 1.3.7 | Laying of SDAC over full length including existing runway and apron full width | cum | 3700 | | | | | | | | | | | | | | | | | |
| 1.3.8 | Laying of DAC over full length, full width including existing runway and apron | cum | 2620 | | | | | | | | | | | | | | | | | |
| 1.3.9 | Pavement connecting terminal to apron including all finishing works full width | mts | 50 | | | | | | | | | | | | | | | | | |
| MILESTONE 1 | | | | | | | | | | | | | | | | | | | | |
| MILESTONE 2 | | | | | | | | | | | | | | | | | | | | |
| MILESTONE 3 | | | | | | | | | | | | | | | | | | | | |
| MILESTONE 4 | | | | | | | | | | | | | | | | | | | | |
| MILESTONE 5 | | | | | | | | | | | | | | | | | | | | |
| MILESTONE 6 | | | | | | | | | | | | | | | | | | | | |
| MILESTONE 7 | | | | | | | | | | | | | | | | | | | | |
| MILESTONE 8 | | | | | | | | | | | | | | | | | | | | |